

Index
File No. M-04

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor.
No. _____

T 1N R. 36E

R.D. WALLA-WALLA County UMATILLA

Merid. WILLAMETTE

N.F. UMATILLA State OREGON

CORNER DIAGRAM



1 DESCRIBE CORNER MONUMENT FOUND

3 1/4" BRASS CAP ON 2 1/2" IRON PIPE RISING 2"

2 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

24" PONDEROSA PINE BLAZED & SCRIBED SE 1/16 S18 BT
BEARS N 82° E ~ 79 LKS. - 52' FT.

24" PONDEROSA PINE BLAZED & SCRIBED SE 1/16 S18 BT
BEARS N 28° W ~ 23 LKS. - 15' FT.

3 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

CORNER IS ON RIDGE TOP 200 FT NORTH OF
ROAD 3030 AND 200' WEST OF ROAD 3030-020

6 PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature _____

7 PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency _____

Signature

Title

Division

Headquarters

Date

7100-52-(3/68)

R. Sullard

PLS 1848

11-15-84

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET STEEL FENCE POST WITH 54-2 & 54-4 SIGNS ATTACHED -
3FT SOUTH OF CORNER MONUMENT.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

ATTACHED 54-4 SIGNS ON SIDE OF TREES AWAY FROM CORNER,
PAINTED RED BAND AROUND TREES & PAINTED FACE OF BLAZES.

Work Done By B.A. SUTTON Title SURVEYOR Date 11-584 State Registration No. PLS-1848
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T. 1N R. 36E M. WILLAMETTE Tract or Surv. No.

Cor. SE 1/8 S18

M-04