


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-14
420340
T. 1 N., R. 36 E.
CW 1/16 Corner of section 22

History of original corner establishment:

1997-99, Kaiser, Griffin and Seibold, BLM Cadastral Surveyors, established the corner as follows:
Point for the center W 1/16 sec. cor. of sec. 22.
Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground, to solid rock, and supported in a mound of stone, 2 1/2 ft. base, to top, with brass cap, from which
A ponderosa pine, 20 ins. diam. bears N. 10° E., 251 lks. dist., mkd. CW 1/16 S22 BT.
No other bearing trees available within limits.
Deposit a magnet in a white plastic case at the base of the stainless steel post.



2000, David L. Haddock, Registered Land Surveyor 852, while surveying in sections 21 and 22 for the Umatilla N.F., finds evidence of the original 1/4 corner of sections 21 & 22 and the original 1/4 corner of sections 22 & 27. This makes the BLM monument an erroneously established corner.

2001, Richard S. Kaiser, BLM Cadastral Surveyor, corrects the BLM's corner as follows:
Point for the center W 1/16 sec. cor. of sec. 22. From this point, the center W 1/16 sec. cor. of sec. 22, erroneously established by Kaiser, Griffin, and Seibold in 1997-99, bears N. 28°38'18" W., 59.62 ft. dist.; monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 10 ins. above the ground, in a mound of stone, 3 ft. base 1/2 ft. high, with brass cap mkd. and witnessed as described in the official record.
Remove the stainless steel post and magnet and at the true corner point
Reset the stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, in a collar of stone, with brass cap
from which a bearing tree mkd. by Kaiser, Griffin, and Seibold
A ponderosa pine, 20 ins. diam., bears North, 215.5 ft. dist., with scribe marks
CW1/16 S22 BT visible on partially healed blaze.
No other bearing trees available within limits.
Deposit a magnet in a white plastic case at the base of the stainless steel post.

Description of corner evidence found:

Found a 2 1/2" diameter stainless steel pipe, with 3 1/4" diameter brass cap, projecting 6" out of the ground, surrounded by a ring of stones, marked as shown, from which:



20" Ponderosa Pine bears NORTH, 215.6 feet, with scribing visible on pitched over blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

New reference:
RM, 5/8" diameter by 24" long rebar with 1 1/4" diameter yellow plastic cap stamped "UMATILLA N.F.", set 23" in the ground at the base of a rock outcrop 2 feet by 2 feet by 2 feet high, bears N 47°26' E, 44.62 feet.

DATUM: NAD83(1991) Oregon High Accuracy Reference Network
STATE PLANE COORDINATES: Oregon North Zone in International Feet
No. Latitude Longitude Northing(Y) Easting(X)
420340 45°33'04.13051" N. 118°18'09.81737" W. 694689.448' 8764906.892'

Work Performed By: David A. Schlaich (RLS 2308)
Witnessed By: Matthew Duffy
Equipment: Topcon GPT-6005C Total Station
Magnetic Declination: 17 1/2' East
Date: September 3, 2002

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2004

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 20.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)