

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. E-1


**History of original corner establishment:**

Record of the original survey by Jacob C. Cooper, 1881 states: Set post, 4½ ft. long, 4 ins. square, 2 ft. in the ground on E. side of mountain 600' above valley lying E. for cor. to secs. 1,6,7, and 12, marked T1N S6 on NE, R38E S7 on SE, R37E S12 on SW, and S1 on NW with 5 notches S and 1 notch N, from which:

A Fir 10" diam. bears S10°E 98 lks. dist, marked T1N R38E S7 BT.

A Pine 36" diam. bears N27°E 144 lks. dist, marked T1N R38E S6 BT.

No other trees in limits, raise mound of stone alongside.



**Description of corner evidence found:**

Found remains of stone mound. Established true corner point at record bearing and distance to the only remaining original bearing tree, an original 36" now 49" Ponderosa Pine, alive with scribing "38S6" on a partially-healed blaze bears N27°E, 95.0 ft.

**Description of monument and accessories established to perpetuate the original location of this corner:**


At the true corner point, set a 2"x30" galvanized Iron Pipe, 15" in the ground to bedrock, and construct a stone mound 3' diam. at base to top of cap, with brass cap attached, marked:

From which we mark new BT's:

A 22" Douglas Fir bears S77°E 25.5 ft. scribed "T1N R38E S7 BT" on a double blaze,

A 10" Douglas Fir bears N27½°W 46.3 ft., scribed "T1N R37E S1 BT" on a double blaze,

A 20" Douglas Fir, bears S36°W 78.6 ft., scribed "T1N R37E S12 BT" on a double blaze



Attached brass washer, stamped "LS 1099" to lower blaze of new BT's.

Placed steel fencepost 5 ft. north of corner with sign 54-4 attached.

Attached signs and painted all BT's per Standard Specifications For Cadastral Survey, U.S.F.S. Region 6, Oct., 1979.



Witnesses: Gary Langlitz  
Tom Isaacson  
Loren Huntsman

Compass Declination: 19½° East

I hereby certify the corner monument and accessories described above were established on August 7, 1980.

Office of.....County Surveyor..... County of.....Wasilla.....

State of.....Oregon..... I hereby certify that the within instrument was filed in this office

for record on the..... day of.....January....., 19.....81

.....David Kumbier..... by.....Betty Smith.....

(COUNTY OFFICIAL) (DEPUTY)