

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-1


History of original corner establishment: Record of the original survey by J. Cooper, dated 1881.

States:

40 DO Chs. Set post 3 ft. long, 3 ins. sq., 18 ins. in the ground, on a steep N hillside in Fir timber and dense undergrowth for 1/4 Sec. Cor. marked 1/4 S on the E and W faces, from which:


- A Fir, 13 ins. diam. bears S40°W 13 lks. dist., marked 1/4 S BT.
- A Spruce, 8 ins. diam. bears S33°E 34 lks. dist., marked 1/4 SBT

42.75 chains. Spring branch course East. Ascend through heavy timber and undergrowth.



Description of corner evidence found: No trace of the original corner post or bearing trees could be found. We do find a well-defined line of blazes running N-S, and open one North of the corner point, which is 95-100 years old by ring count. We therefore establish the True Corner Point as follows:

At 2.75 chains south of a well-defined spring branch, Course E, on a steep N hillside and at a mean E-W position along the found line of N-S blazes, we set a 2"x30" Galvanized Iron Pipe, 28" in the ground, with brass cap attached, marked:



Description of monument and accessories I established to perpetuate the original location of this corner:

From which we mark new Bearing Trees:

- A 16" Grand Fir, scribed "1/4 S12 BT" on a double blaze bears N74°W 29.8 ft.,
- And a 22" Spruce, scribed "1/4 S7 BT" on a double blaze bears S10°E 15.5 ft.

Attached brass washer stamped "LS 1099" to lower blaze of new BTs.

Placed steel fence post 5 ft. South of monument with sign 54-4 attached.

Attached signs and painted BTs per Standard Specifications for Cadastral Survey, U.S.F.S. Region 6, October, 1979.

Compass Declination: 20° East.

I hereby certify the above corner monument was established as herein described on September 29, 1980.

Witness: John Curtiss



Gary L. Langlitz
 OREGON
 JULY 22, 1977
 GARY L. LANGLITZ
 1099

Office of..... County Surveyor..... County of..... Umatilla
 Oregon
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 1980.
David Kumbler by *Betty Smith*
 (COUNTY OFFICIAL) (DEPUTY)