

R-3

OREGON CORNER RESTORATION FORM

Section 30 Township 1 N Range 37 E.

County Umatilla Date Sept., 1993

CORNER DESIGNATION

1/4 corner common to 19/30
corner index: R-3

<input type="checkbox"/>	Condition Report Only
<input type="checkbox"/>	Not Found
<input type="checkbox"/>	Renewed
<input type="checkbox"/>	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input type="checkbox"/>	Referenced Out

Previous Renewals/Surveys, etc.

1882 Herman Gradon, set a basalt stone 18"x10"x4", 12" in the ground, marked with a 1/4 on the north face, from which;

4" cherry bears N.25°E., 13.2 feet scribed per manual of instruction.
20" fir bears S.10°W., 40.3 feet scribed per manual of instruction.

Monument(s) & Accessories Found: (Condition and Source)

No evidence was found at various search positions. Search areas included record distances from each section corner and the short 1/2 mile distances as measured on the east and west section line. The topo calls on this line are to general to be of any use.

Monument Detail

Sketch



Monument Set (Procedures and Description)

At a single proportion position I set a 3-1/4" aluminum cap on a 2-1/2"x 30" aluminum pipe, 28" in the ground, with a small rock cairn, with a land survey monument sign attached to a steel post nearby.

New Accessories

- 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24" rebar bears S.49-1/2°W., 13.6 ft, cap is stamped 13.6 RM with an arrow pointing toward the corner.
- 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24" rebar bears N.9°W., 14.5 feet, cap is stamped 14.5 RM with an arrow pointing toward the corner.
- 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24" rebar bears N.41°E., 18.5 feet, cap is stamped 18.5 RM with an arrow pointing toward the corner.
- 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24" rebar bears S.22°E., 13.2 feet, cap is stamped 13.2 RM with an arrow pointing toward the corner.

Location & Comments

 RECEIVED BY _____
 Umatilla County _____
 Date 12-93
 Rec'd By RR
 No. 93-93-B

Compass Declination 18° east
 Firm/Agency: White Shield, Inc
 Address: P.O. Box 477,
Grandview, WA 98930
 Party Chief: Dennis Hartmans
 Notes field bk. 3, pg.5
 Witness Wes Cochran

Surveyor's Seal

