

USDA-FOREST SERVICE

Index File No. T-5

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T IN R. 37E

R.D. Walla Walla County Umatilla

Merid. W.M.

N.F. Umatilla State OR

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

ON STEEP WEST SLOPE

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Michael P. Ziegler

P.L.S.

Division _____ Headquarters _____

Date *10/93*

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At single proportion set A 3/4" aluminum cap on a 2 1/2" x 30" aluminum pipe, 24" in the ground w/rock cairn

T1N R37E
1/4
S30 f S29
PLS 2535
1993

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

21" Douglas bears S. 30 1/2° W., 10.3' scribed 1/4 S30BT

10" Douglas fir bears S. 48° E., 21.5' scribe 1/4 S29BT

1 1/2" aluminum cap (PLS 2535) on a 5/8" x 24" rebar bears N. 42 1/2° E., 14.1 ft.

1 1/2" aluminum cap (PLS 2535) on a 5/8" x 24" rebar bears N. 20 1/2° W., 12.7 ft.

Work Done By LeJeune Title P.L.S. Date 9/93 State Registration No. 2535
or Agency

Certified Cor. Record Prepared Yes No Filed At: _____ Date _____

REMARKS

Index File No. T. R. M. Tract or Surv. No. Cor.

T-5

T. 1N

R. 37E

M. W.M.