

Index

File No. U-0125

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or

Survey No. \_\_\_\_\_

Cor.

No. \_\_\_\_\_

T 1N R. ~~27E~~ 36E

R.D. WALLA WALLA


County UMATILLA

Merid. WILLAMETTE

N.F. UMATILLA

State OREGON

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

Corner not previously established.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

Corner not previously established.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Signature*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner falls on a very steep brushy East face approximately 250 feet West of a draw and approximately 1300 feet South of the North Fork of Meacham Creek.

Title  
**Surveyor**

Division \_\_\_\_\_

Headquarters \_\_\_\_\_

Date  
**9-19-89**

FS-7100-52 (3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:  
Pipe is set 30 inches in the ground.

T1N  
R36E R37E ¼  
S 1/16  
|  
S 25 | S 30  
1989  
OPLS 644

**ACCESSORIES : DESCRIBE NEW BTs WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

**New Bearing Trees:**

A 10 inch diameter Douglas Fir bears S33°E, 16.80 feet marked S1/16 S30 BT  
A 13 inch diameter Douglas Fir bears S12°W, 50.5 feet marked S1/16 S25 BT.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fence post approximately 5 feet South with 54-9 and 54-2 signs attached.

Work Done By D.I. Griffith Title Surveyor Date 9-12-89 State Registration No. OPLS 644  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla Co. Surveyor's Office Date 9-89

**REMARKS**

Witness: Jeff Petersen