

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

THIS CORNER WAS ORIGINALLY ESTABLISHED BY GENERAL LAND OFFICE SURVEYORS WILLIAMS & PERSHIN UNDER CONTRACT NO. 154 DATED JUNE 6, 1871.

SURVEYOR GENERAL LAND OFFICE FIELD NOTES STATE:  
 "SET A STONE 22x7x4 ON N.W. SIDE OF SPUR FOR CORNER TO SEC. 21, 22, 27 AND 28."

SURVEY NO. 252 BY JOHN W. KIMBRELL DATED APRIL 10, 1907 STATES "COMMENCING AT THE COR. TO SECTIONS 21, 22, 27 & 28, A STONE MARKED ORIGINAL CORNER"

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

FOUND A 22"x7"x4" STONE WITH 4 NOTCHES ON NORTHEAST CORNER AND 3 NOTCHES ON SOUTHEAST CORNER, BURIED 1.0' IN THE GROUND.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:**

THIS CORNER WAS PERPERUATED BY SETTING A 5/8"x30" IRON ROD WITH 3-1/4" ALUMINUM CAP SET FLUSH AT THE LOCATION WHERE THE STONE WAS RECOVERED. THE ORIGINAL STONE WAS BURIED ALONGSIDE ON THE NORTH SIDE OF THE CAP.

THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS N 42°32'41" E, 18.89 FEET.
- 2) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS S 71°53'45"E E, 21.70 FEET.
- 3) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS S 31°55'39" W, 12.61 FEET.
- 4) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS N 73°17'29" W, 17.48 FEET.

WITNESSES:  
 BRENT REYNOLDS, LSIT  
 TRAVIS COFFELT

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON MAY 3, 2021.



REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Bret N. Elithorp*  
 OREGON  
 JAN 14, 2003  
 BRET N. ELITHORP  
 61348

EXPIRES: 12/31/2021



OREGON DEPARTMENT  
 OF TRANSPORTATION  
 REGION 5  
 SURVEY  
 UNIT

Section	VINSON CANYON QUARRY		
Highway	HEPPNER HIGHWAY		
County	UMATILLA	Scale	NTS
Purpose	BOUNDARY SURVEY	Date	MAY 27, 2021

21-064-8