


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY GENERAL LAND OFFICE SURVEYORS WILLIAMS & PERSHIN UNDER CONTRACT NO. 154 DATED JUNE 6, 1871.

SURVEYOR GENERAL LAND OFFICE FIELD NOTES STATE:
"SET A STONE 18x8x6 ON N.E. HILLSIDE FOR 1/4 SECTION CORNER."

DIAGRAM



T-17

DESCRIPTION OF CORNER EVIDENCE FOUND:

FOUND A 18"x8"x6" STONE BURIED 1.0 FOOT, CLEARLY MARKED "1/4" CHISELED INTO WEST FACE. STONE WAS FOUND IN ROCK MOUND IN NORTH - SOUTH FENCE LINE.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

THIS CORNER WAS PERPERUATED BY SETTING A 5/8"x30" IRON ROD WITH 3-1/4" ALUMINUM CAP SET FLUSH AT THE LOCATION WHERE THE STONE WAS RECOVERED. THE ORIGINAL STONE WAS BURIED ALONGSIDE ON THE NORTH SIDE OF THE CAP.

THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS N 9°02'58" E, 22.36 FEET.
- 2) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS S 23°57'18" E E, 42.28 FEET.
- 3) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS S 29°24'12" W, 48.12 FEET.
- 4) A 5/8" X 30" IRON ROD WITH RED PLASTIC CAP STAMPED "ODOT CONTROL" BEARS N 44°30'54" W, 35.01 FEET.



WITNESSES:
BRENT REYNOLDS, LSIT
TRAVIS COFFELT

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON MAY 6, 2021.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

BEC
OREGON
JAN 14, 2003
BRET N. ELITHORP
61348

EXPIRES: 12/31/2021



OREGON DEPARTMENT
OF TRANSPORTATION
**REGION 5
SURVEY
UNIT**

Section	VINSON CANYON QUARRY		
Highway	HEPPNER HIGHWAY		
County	UMATILLA	Scale	NTS
Purpose	BOUNDARY SURVEY	Date	MAY 27, 2021

21-064-B