

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla

DATE: 3/4/94

CORNER DESIGNATION: V-13. N.E. Corner Section 33, T1S., R30E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: The original survey was made by George Williams and George S. Pershin under contract No.154, dated June 6th, 1871. Original notes state a 22 X 9 X 6 stone was set for the corner.

MONUMENT & ACCESSORIES FOUND: There are remnants of an ancient East-West fence passing through the corner area. The area South of the corner area has been farmed. Found old rock corner jack at suspected corner location. A investigation of stones in the rock jack revealed the original corner stone measuring 22" X 9" X 6" with visible notches. Re-established the corner point at corner of the rock jack.

**MONUMENT MARKING DETAIL:**

T1S	R30E
S28	S27
S33	S34

1994  
PLS 1106

MONUMENT SET: Set a 2 1/2" brass cap on 1 1/4" X 30" galvanized iron pipe, 24" in the ground, with a mound of stone to the cap. Placed corner stone in the mound, North of the monument.

**New Accessories:**

- A 5/8" X 30" iron pin with a 1 1/2" plastic cap stamped 'WR WELLS PLS 1106' bears N 60° E, 23.7 feet.
- A 5/8" X 30" iron pin with a 1 1/2" plastic cap stamped 'WR WELLS PLS 1106' bears S 35° E, 28.2 feet.
- A 5/8" X 30" iron pin with a 1 1/2" plastic cap stamped 'WR WELLS PLS 1106' bears S 38° W, 30.1 feet.
- A 5/8" X 30" iron pin with a 1 1/2" plastic cap stamped 'WR WELLS PLS 1106' bears N 78° W, 27.7 feet.

Set 6' steel fence posts near each iron pin, attached bearing object signs to each pin and a witness sign to each guard post. Attached a witness sign to the corner post of the rock jack.

**LOCATION AND COMMENTS:**

COMPASS DECLINATION: 18° East  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 12-31-94*

**RECEIVED BY**

Umatilla County Surveyor

Date 7-94

Rec'd By KK

No. 94-82B