

OREGON CORNER RESTORATION FORM

T1N R31E Z1

Section 31, Township 1N, Range 31E,
County Umatilla, Date November 15, 2004.

- Condition Report
- Not Found
- Remonumented
- Unrecorded
- Surveyed in
- Referenced out

Township corner common to Township 1 North Ranges 30 and 31 East and Township 1 South, Ranges 30.5 and 31 East, W.M., Umatilla County.

Previous Renewals / Surveys, etc.

The corner was originally set by David P. Thompson under Contract No. 79 dated July 26, 1858. His record Reads: Set post for corner to Township 1 North, Ranges 30 & 31 East and build a mound of earth as per instructions. Surveyor David Haddock, under survey 01-206-C, found a deposit of decayed wood based on the projections of the North and West lines of Township 1 South, Range 31 East. His record reads: set a 5/8" x 24" iron rebar with a 1 1/4 red plastic cap 30" below the surface. Over the rebar I set a 30" x 1 1/2" G.I.P. with a 2 1/2" brass cap flush with the surface of the ground. I set a 5' steel guard post with a County Monument sign attached along side.


For the references set by Mr. Haddock see his corner certificate.

Monument and accessories found: (Condition and source)

I found the brass cap set by Dave Haddock in good condition. I did not look for the references. The area appears undisturbed.

DIAGRAM

SKETCH



Monument and accessories set: (Procedures and description)

None.

Location and Comments
SPC Oregon North, NAD 83-91
Northing = 677,774.58 ift
Easting = 8,587,216.68 ift

Compass Declination

Surveyor's Seal

Witnessed By:
RECEIVED BY:
Umatilla County Surveyor
Date: 5-05
Rec'd By: KK
No. 05-111-C

Firm / Agency
Witness Tree Surveying
P.O. Box G
Pilot Rock, OR 97868
Party Chief
Stephen K. Haddock, PLS

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Stephen K. Haddock

OREGON
JULY 8, 2001
STEPHEN K. HADDOCK
56295L9

RENEWAL DATE 6-30-05