


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 12, 1864, under GLO contract No. 107, as follows:

Set a stone 16" x 12" x 8" for the 1/4 section corner.



Description of corner evidence found:

A mound of small stones at the corner point. None are over 8" in maximum size and none are marked. I excavate to set an iron pipe monument and 8" below the surface, in loamy soil, I hit the top of a stone, 11" x 3" x 3", standing in an up-right position. This stone is marked "1/4" on the west face. I accept the point occupied by this marked stone as the original corner point.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the exact point occupied by the above described marked stone, I set a 1 1/2" x 30" iron pipe, 26" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S36 NE", attached at ground level, bears N56°E, 89.1 feet.

A 5/8" x 36" iron rod set 31" into the ground to refusal with a 3/4" brass washer, marked "PLS 1636 S36 SE", attached at ground level, bears S35°E, 78.8 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 S35 SW", attached at ground level, bears S34°W, 88.1 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S35 NW", attached at ground level, bears N67°W, 55.5 feet.

I hereby certify the above corner monument was perpetuated as hereon described on March 2, 1997. Magnetic declination: 20° E.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Dennis L. Gaylord*

OREGON JULY 14, 1986 DENNIS L. GAYLORD 1636

Office of COUNTY SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office

for record on the 11 day of March, 1997

*David H. Kline* by \_\_\_\_\_

(COUNTY OFFICIAL)

(DEPUTY)

*Renews 6/30/97*

RECEIVED BY

Umatilla County Surveyor

Date 3-97

Rec'd By AK

No. 97-38-R