

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


---

History of original corner establishment:

Index: J-13

Corner, Secs. 9, 10, 15, & 16, T1S, R32E, WM.

Corner originally set by Daniel Chaplin in contract 107 dated Sept, 21, 1864, his record reads:  
Set post for Cor. to secs 9, 10, 15, and 16, in mound of earth with charred stake, pits, trench, etc. as per instructions.



Description of corner evidence found:  
None

Description of monument and accessories I established to perpetuate the original location of this corner:  
The corner was set at the intersection of the line of a fence which runs to the North with the centerline of County Road No. 1150. This location was indicated in the County Road Survey and was found acceptable. I set a 1 1/2"x24" Galvanized Iron Pipe with a 2 1/2" Brass Cap in a 8"x24" concrete cylinder, 1" below the surface of the asphalt in the center of the right of way of County Road 1150, stamped as in the diagram above.  
A 5/8"x24" rebar with 2" Al cap bears S89°59'E, 30.0', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears N1°01'E, 28.9', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears N89°16'W, 30.1', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears S02°21'E, 29.0', stamped B.O., ORLS 852, AND WALS 13922.  
The bearings are based on the fence line to the north being north.

This work was done September 27, 1995 and witnessed by Stephen Haddock.

Office of Survey Dept. County of Umatilla  
State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 23<sup>rd</sup> day of October, 1995.  
\_\_\_\_\_  
( COUNTY OFFICIAL ) by \_\_\_\_\_ ( DEPUTY )

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1988  
DAVID L. HADDOCK  
852

RECEIVED BY  
Umatilla County Surveyor  
Date 10-95  
Rec'd By KK  
No. 95-185-R