

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


---

History of original corner establishment:

Index: N-13

Corner, Secs. 15, 16, 21, & 22, T1S, R32E, WM.

Corner originally set by Daniel Chaplin in contract 107 dated Sept, 21, 1864, his record reads:  
Set post for Cor. to secs 15, 16, 21, and 22, in mound of earth with charred stake, pits, trench, etc. as per instructions.



Description of corner evidence found:  
None

Description of monument and accessories I established to perpetuate the original location of this corner:

The corner is at the intersection of a fence which runs East and West with a fence that runs to the south. This fence corner was called acceptable and used in survey Q-863-B by PLS 346. I set a 1 1/2"x30" Galvanized Iron Pipe with a 2 1/2" Brass Cap for a witness corner 5' West of the true corner point on line stamped as in the diagram above. The witness monument and the bearing objects are recorded in relation to the true corner location.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1968  
DAVID L. HADDOCK  
852

A 5/8"x24" rebar with 2" Al cap bears S01°20'W, 30.0', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears N0°00'E, 1.5', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears N88°51'W, 30.0', stamped B.O., ORLS 852, AND WALS 13922.  
A 5/8"x24" rebar with 2" Al cap bears S89°32'E, 30.0', stamped B.O., ORLS 852, AND WALS 13922.  
The bearings are based on the section line to the south being S00°28' 33" W.

This work was done September 27, 1995 and witnessed by Stephen Haddock.

Office of Survey Dept. County of Umatilla  
State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 23<sup>rd</sup> day of October, 1995.  
\_\_\_\_\_  
( COUNTY OFFICIAL ) by \_\_\_\_\_ ( DEPUTY )

RECEIVED BY  
Umatilla County Surveyor  
Date 10-95  
Rec'd By KK  
No. 95-186-R