

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/03/99

CORNER DESIGNATION: J-7, The North Quarter Corner of Section 17, T1S., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Currin and Noland under Special Contract, dated May 4, 1887. Notes state: Set basalt stone, 14 x 10 x 8 ins., 8 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on N. face. Raised mound of stone around it. Pits impracticable.

MONUMENT AND ACCESSORIES FOUND: None. Found rock jack fence corner with old fences running East, West and North. A fence on line is visible about 1/2 mile South, across Little McKay Creek Canyon. Several stones of approximate record size were found in rock jack, but no stone markings were noted.

MONUMENT MARKING DETAIL:

T1S R33E  
1 S8  
4 S17  
1999  
PLS 1106

MONUMENT SET:

At the corner of the fence jack, drove a 5/8" by 24" iron pin 8" into ground and rock and surrounded with a mound of earth and stone. Placed a 1 1/2" aluminum cap on the iron pin, marked as shown in Monument Marking Detail. A iron pin monument was used instead of a standard flanged monument because a standard monument will not hold in the rocky ground.

New accessories:

"XBO" chiseled on a rock outcrop at ground level (6 x 10" exposed), bears N 24° E, 13.9 feet. Measured to "X" on the chiseled marks.

A 1/2" x 15" iron pin driven to bedrock, bears S 39° E, 23.3 feet, with bearing object tag attached.

A 1/2" x 15" iron pin driven to bedrock, bears S 54° W, 18.3 feet, with bearing object sign attached.

A 3/4" brass washer, marked "PLS 1106", nailed to the southwest corner of wood rock jack, 6" above ground, bears N 79° W, 3.7 feet.

Nailed "Witness Corner" sign to wood rock jack North of corner monument.

LOCATION AND COMMENTS: Corner is located on a ridge top at a rock jack fence corner with fences extending North, East and West.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: William R. Wells, PLS  
Jason Wells

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

RENEWS 6-30-00

RECEIVED BY  
Umatilla County Surveyor  
Date 6-99  
Rec'd By JK  
No. 99-81-B