

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/5/94

CORNER DESIGNATION: A-1. Northwest corner Section 6, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by L.E. Wilkes, under Contract No. 29, dated Feb. 20, 1917. Notes state: "Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. deep among rocks on steep E. slope, for closing cor. of secs. 1 and 6, with brass cap (marked as shown in monument detail) from which

A cross (x) on a basalt stone, a part of irregular bluff facing N., bears S.19°E., 25 lks. dist., with C C 6 B O marked beside the cross. A cross (x) on a basalt stone in place, 1x1x1 ft. above ground, bears S. 54°W., 11 lks. dist., with C C 1 B O marked beside the cross."

MONUMENT AND ACCESSORIES FOUND:

A 2 1/2" brass cap on 2" galvanized iron pipe, on east edge of basalt outcropping, protruding 8" out of ground, (marked as shown in monument detail). Impractical to rebuild mound, nearly vertical on East side. From the found monument: Faint chisel marks on a 1' x 1' x 1' rock outcrop bear S 54° W - 7.3 feet. Marks "1 B" are visible (Wilkes bearing object).

MONUMENT MARKING DETAIL:

U.S. G L O SURVEY
T1N
R34E
S31

S1 | S6
R33E | R34E
T1S
1917

MONUMENT SET:

New accessories to existing corner monument:
Set steel fence post 1.2 feet North of monument with witness post attached.
"XBO" chiseled on 1' x 1' x 1.5' outcropping bears S 24° E-7.2 feet, on a smooth surface on top of outcropping.
"XBO" chiseled on 2' x 3' x 5' outcropping bears S 16° E-21.7 feet, on smooth surface on top of outcropping.
"XBO" chiseled on 3.5 x 3.0 x 2.5 outcropping bears S 21° W-15.6 feet on smooth vertical face 0.5 feet from base.
"XBO" chiseled on 2.0 x 1.0 x 1.0 outcropping bears S 46° W-13.7 feet on smooth surface on top of outcropping.
Measured to "X" on "XBO" marks.

LOCATION & COMMENTS:

Corner is located South of East-West fenceline.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 679565.18
E = 8685804.25

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Willie R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By JK

No. 95-16-C