

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/19/94

CORNER DESIGNATION: A-13. Northeast corner Section 4, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Closing Cor. to Secs. 3 & 4, marked CC. with 3 notches on E. & W. edges, and raised mound of stone around it."

MONUMENT AND ACCESSORIES FOUND: Found railroad tie post at corner position. 'Red' Marvin Anderson stated he had set it at the corner position so it wouldn't be lost. I verify the location of the post by survey and accept as the best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T1N R34E
CC

S4 | S3
T1S R34E
1994
PLS 1106

MONUMENT SET: At the edge of the existing railroad tie post, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 29" in the ground, (marked as shown in the monument detail).

New Accessories:

- Attached witness sign to railroad tie post.
 - A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 61° E-18.2 feet, top buried 10" under ground surface.
 - A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 30° E-13.8 feet, top buried 11" under ground surface.
 - A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 15° W-25.8 feet, top buried 11" under ground surface.
 - A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 56° W-19.7 feet, top buried 12" under ground surface.
- Attached bearing object sign to each pin. Set steel fence post with witness sign attached near each pin.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:
Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 679983.66
E = 8701795.87

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C