

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/08/95

CORNER DESIGNATION: A-25. Northeast corner Section 1, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by James P. Currin and James E. Noland, under Special Contract, dated May 4, 1887.

Surveyor General records state:

Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground for Closing Cor. to Tps. 1 S., Rs. 34 & 35 E., marked 6 notches on S.E. and W. edges and C.C. on S. face, from which:

A pine, 12 ins. diam., brs. S. 40° E., 190 lks. dist. marked T.1S., R.35E., S.6, C.C., BT.

A pine, 20 ins. diam., brs. S. 20° W., 208 lks. dist., marked R.34E., S.1, C.C., BT.

No other trees in limits.

MONUMENT AND ACCESSORIES FOUND: A mound of stone at corner position and a decayed pine stump which bears S 20° W, 208 lks, (137.3 ft), per record for Section 1.

MONUMENT MARKING DETAIL:

AM  
T1N R35E  
S31  
--- ---  
S1 | S6  
CC  
T1S  
1995  
ORLS 1106

MONUMENT SET: At position of recovered mound of stone, set a 2 1/2" brass cap on a 1 1/2 in. x 30 in. galvanized iron pipe, projecting 6 in. with a 2 foot diameter mound of stone (marked as shown in the monument detail).

From which:

The decayed 30 in. pine stump (original bearing tree) bears S 20° W, 137.3 feet.

New Bearing Objects:

A 7 in. ponderosa pine with double blaze scribed "T1S R35E S6 AM BT" bears S 47° E., 71.1 feet.

A 12" ponderosa pine with double blaze scribed "T1S R34E S1 AM BT" bears S 28° W, 108.5 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106-WA PLS 17372" bears N 42° E, 20.2 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 39° W, 22.1 feet.

A 1/2" brass washer marked "PLS 1106" was nailed to lower blaze of each bearing tree.

Attached bearing object signs to each iron pin, set steel fence post near each corner monument with witness sign attached.

LOCATION & COMMENTS: Corner falls 10 feet North of forest road. Amended monument is located N 00°21'40" Em 4.64 feet from South line of Section 31.

STATE PLANE CO-ORDINATE:

Oregon North, NAD 83/91, U.S. Survey Foot:

N = 680346.17

E = 8717638.79

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Witness: William L. Hanley, PLS

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6/30/96*

RECEIVED BY

Umatilla County Surveyor

Date KK

Rec'd By 2-95

No. 95-16-c