


History of original corner establishment:

Original corner established by James E. Noland on July 2, 1887, under special contract, as follows:

Set a post for the corner, from which:

- A 6" pine bears N70°E, 53 links (34.98 feet).
- A 14" pine bears S45°E, 87 links (57.42 feet).
- A 8" pine bears S20°W, 87 links (57.42 feet).
- A 16" pine bears N34°W, 63 links (41.58 feet).



Description of corner evidence found:

A 27" Ponderosa Pine with scribes "S2" visible on a previously opened upper blaze, lower blaze healed. Bears N34°W, 41.6 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the one remaining original bearing tree, set a 1" x 30" iron pipe 16" into the ground to bedrock. Built a mound of stones around the pipe. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 13" Ponderosa Pine, scribed "T1S R34E S1 BT", bears N8°E, 61.6 feet.
- A 21" Ponderosa Pine, scribed "T1S R34E S12 BT", bears S79°E, 69.7 feet.
- A 14" Ponderosa Pine, scribed "T1S R34E S11 BT", bears S23°W, 28.5 feet.

The three new bearing trees are scribed on double blazes, have a 5/8" brass washer, marked "PLS 1636", nailed flush to the lower blaze and have a bearing tree sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on November 23, 1995. Magnetic declination: 20°E.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Dennis L. Gaylord*

**OREGON**  
JULY 14, 1978  
**DENNIS L. GAYLORD**  
1636

*Renews 6/30/97*

Office of...*The Survey Dept*... County of...*Umatilla*...  
 State of...*Oregon*... I hereby certify that the within instrument was filed in this office  
 for record on the...*28*... day of...*November*... , 19*95*

(COUNTY OFFICIAL)

by

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date *11-95*

Rec'd By *XX*

No. *95-207-R*