


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-25

History of original corner establishment:

Original survey by Currin and Noland under their special contract, 1887, Set a Basalt Stone 9x8x7 ins. 6 ins. in the ground for 1/4 Sec. Cor., mkd. 1/4 on W. face, from which: A Pine 20 ins. diam. bears N 25°E 83 lks. dist. mkd. 1/4 S BT. A Pine 20 ins. diam. bears N 45°W 125 lks. dist. mkd. 1/4 S BT.




NOTE: Subdivisions of T1S R35E by Currin, Et Al, 1887 established closing corners on the line between Ranges 34 and 35 East for the survey lines in T1S R35E.

Description of corner evidence found:

A Basalt stone 9"x8"x7" with chisel markings "1/4" on a face, lying loose in a mound of stones approx. 2 ft. in diameter and 6" high, From which: A sawn Ponderosa Pine stump, rotted, approx. 20" dia. no marks visible bears N 22 1/2°E 56.3 ft. (54.8 ft. to face) and a sawn Ponderosa Pine stump rotted, approx. 20" dia. no marks visible, bears N 37°W 83.3 ft. (82.5 to face)

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point in place of the found corner stone in stone mound, we set a 2"x30" galvanized iron pipe, 20" in the ground and in a mound of stone 2' base and 1' high with brass cap attached marked: Bury original corner stone along iron pipe from which: We mark new bearing trees: A 10" Ponderosa Pine, scribed "1/4 S13 BT" on a double blaze bears N 49 1/2°W 23.3 ft., and a 10" Ponderosa Pine, scribed "S18 BT" on a double blaze bears N63 1/2°E 24.5 ft.



Attached brass washer marked "LS 1099 to lower blaze of new BT's. Bearing and horizontal distance measured to center of bearing tree at ground level.

Staff Compass (19 1/2° East Declination) Steel Tape

October 4, 1983 Witnesses: Gary Langlitz LS 1099 Dick Humiston



Office of Surveyor County of Multnomah State of Oregon I hereby certify that the within instrument was filed in this office for record on the 11th day of November 1983 by Daniel Humiston by Betty Cochran (DEPUTY)