

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/27/95
CORNER DESIGNATION: E-15. North 1/4 corner Section 10, T1S., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by Thompson & Chaplin under Contract #104 dated April 16, 1864.

Surveyor General records state:

Set post for 1/4 Sec. Cor., from which,

A spruce, 12 ins. diam., brs. S.5°W., 27 lks. dist.

A spruce, 12 ins. diam., brs. N.30°W., 12 lks. dist.

Corner remonumented by by Currin & Noland under Special Contract dated May 4, 1887. Surveyor General records state:

To a point 14 lks. N. of 1/4 Sec. Cor., which I found burned and bearing trees partly destroyed, from thence I

Set a post 30 x 3 x 3 ins., 24 ins. in ground, marked 1/4 S. on N. face, from which,

A tamarack, 36 ins. diam., brs. N.45°W., 117 lks. dist. marked 1/4 S., B.T.

MONUMENT AND ACCESSORIES FOUND: A sawed tamarack stump with 36" diameter log alongside, burned face with blaze and chaining notch, bears N 45° W, 70.2 feet (117 links per 1887 Currin & Noland record).

MONUMENT MARKING DETAIL:

T1S R35E

1 . S3

4 S10

1995

ORLS 1639

MONUMENT SET:

Set a 1" diameter by 30" long galvanized iron pipe with a 2 1/2" brass cap, projecting 6" out of the ground in surrounding rock mound, marked as shown in monument marking detail.

Monument has a 6' steel fence post alongside with witness sign attached.

A 9" diameter lodgepole pine bears N 67° E, 21.0 feet, scribed "1/4 S3 BT" on double blaze.

A 12" diameter lodgepole pine bears S 61° E, 48.6 feet, scribed "1/4 S10 BT" on double blaze.

A 9" diameter lodgepole pine bears S 06° W, 82.8 feet, scribed "1/4 S10 BT" on double blaze.

A 9" diameter lodgepole pine bears N 72° W, 49.5 feet, scribed "1/4 S3 BT" on double blaze.

Each new bearing tree has a Umatilla County bearing tree sign attached above the upper blaze and a brass washer marked PLS 1639 nailed to the face of the lower blaze, with face of blazes painted red.

Original bearing tree log has a Umatilla County bearing tree tag attached above the blaze, with face of blaze painted red.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East

FIRM/AGENCY: William R. Wells, PLS

P.O. Box 1696

Pendleton, Oregon 97801

Witness: William Hanley, PLS 1639

Dawn Tubbs

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1976
WILLIAM L. HANLEY
1639

RENEWS 06/30/97

RECEIVED BY

Umatilla County Surveyor

Date 12-95

Rec'd By KK

No. 95-221-B