

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 12/27/95  
CORNER DESIGNATION: G-13. East 1/4 corner Section 9, T1S., R35E.,  
W.M.

**PREVIOUS RENEWALS/SURVEYS, ETC.:** Corner originally established by  
Thompson & Chapin under Contract #104 dated April 16, 1864.

Surveyor General records state:

Set post for 1/4 Sec. Cor., from which,

A fir, 6 ins. diam., brs. S.45°E., 16 lks. dist.

A fir, 8 ins. diam., brs. N.65°W., 15 lks. dist.

Corner remonumented by Currin & Noland under Special Contract dated  
May 4, 1887. Surveyor General records state:

I found post down and B.T.s partly decayed. I set post 36 x 3 x 3  
ins., 2 ft. in ground, marked 1/4 S. on W. face, from which,

A tamarack, 10 ins. diam., brs. N.20°E., 30 lks. dist., marked  
1/4 S., B.T.

A fir, 8 ins. diam., brs. S.25°W., 30 lks. dist., marked 1/4  
S., B.T.

**MONUMENT AND ACCESSORIES FOUND:** Found a 29" fir with previously  
opened face 5" deep; opened face 5" deeper and found blaze with  
"4S" scribe [12-20-95 WLH WRW], (bears S 25° W, 30 links - 19.8  
feet per Currin & Noland 1887 record). Found monument by LS 933  
reported on Survey No. S-2-B bears S 86°30' W, 67.1' from corner  
position re-established from recovered Section 9 bearing tree.

**MONUMENT MARKING DETAIL:**

T1S R35E

1/4

S9-|-S10

1995

ORLS 1639

**MONUMENT SET:**

Re-established corner position by record bearing and distance from  
recovered Section 9 bearing tree - this position is in line with  
very old fence lines which run East and South.

Set a 1" diameter by 30" long galvanized iron pipe with a 2 1/2"  
brass cap, projecting 4" out of the ground marked as shown in  
monument marking detail.

Monument has a 6' steel fence post alongside with witness sign  
attached.

A 13" diameter red fir bears N 55° E, 60.5 feet, scribed "1/4 S10  
BT" on double blaze.

A 6" diameter tamarack bears S 64° E, 27.6 feet, scribed "1/4 S10  
BT" on double blaze.

A 7" diameter red fir bears S 80° W, 55.2 feet, scribed "1/4 S9 BT"  
on double blaze.

An 11" diameter tamarack bears N 61° W, 20.6 feet, scribed "1/4 S9  
BT" on double blaze.

Each new bearing tree has a Umatilla County bearing tree sign  
attached above the upper blaze and a brass washer marked PLS 1639  
nailed to the face of the lower blaze, with face of blazes painted  
red.

Original bearing tree has a Umatilla County bearing object tag  
attached above the blaze, with face of blaze painted red.

**LOCATION & COMMENTS:**

**COMPASS DECLINATION:** 18° East

**FIRM/AGENCY:** William R. Wells, PLS

P.O. Box 1696

Pendleton, Oregon 97801

Witness: William Hanley, PLS 1639

Dawn Tubbs

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

RENEWS 06/30/97

**RECEIVED BY**

Umatilla County Surveyor

Date 12-95

Rec'd By KK

No. 75-221-B