


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.
See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the original location of this corner: At position determined by survey, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26 inches in the ground, from which:


New Bearing Trees:
A 16 inch diameter Ponderosa Pine bears S65°W, 73.54 feet marked ¼ S2 BT
A 14 inch diameter Ponderosa Pine bears N38°W, 7.65 feet marked X BT
(No other trees available to the South)

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fence post approximately 5 feet East with Land Survey Monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on September 14, 1989.

Witnesses: Rick Robinson and Jeff Petersen



Duane I. Griffith
OREGON
JULY 16, 1984
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of *the Survey Dept* County of *Umatilla*
State of *OR* I hereby certify that the within instrument was filed in this office
for record on the *27* day of *October*, 19 *89*
David R. Krumbein by *Kathleen K. Armstrong*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

*GPO-591-971, 1988

Date *10-89*
Initials *KA*
No. *89-101-B*