


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by Jacob C. Cooper under GLO contract number 397, dated July 1, 1881. Surveyor General record states:  
 Intersect the base line 21.90 chs E. of cor to Tps 1 N. Rs 36 and 37E. Set post 4 1/2 ft. long 4 ins square 24 ins in the ground for closing cor to Tps 1 S. Rs 36 and 37 E. marked CC T1S on the S. R37E S6 on the E. and R36E S1 on the West faces with 6 notches on the S, E and W faces.  
 A tamarack 20 ins diam bears S65°W 17 lks dist marked T1S R36E S1 BT.  
 A tamarack 13 ins diam bears S41°E 35 lks dist marked T1S R37E S6 BT



No record of subsequent monumentation found in Umatilla County survey records.

**Description of corner evidence found:**

Found a 10 ft. chunk of 14-16 inch diameter Western Larch with blaze and chop marks with very faint scribes visible. Impossible to determine the exact origin of the tree, as the area has been violently torn up by logging.

I place this corner at the intersection of the base line between Townships 1 North and 1 South, and the projected East line of Section 1. This position is harmonious with the area of the found bearing tree, the spring branch call to the East, and also with the existing blaze line to the South. There is an excess along the base line of approximately 3 chains, which would make a true proportionate position for this corner in conflict with the existing conditions.

See map of survey dated September, 1989.

**Description of monument and accessories I established to perpetuate the**

**original location of this corner:** At the above described corner position, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

**New Bearing Trees:**

A 25 inch diameter Western Larch bears S55°E, 187.45 feet marked T1S R37E S6 CC BT  
 A 22 inch diameter Hemlock bears S15°E, 54.10 feet marked T1S R37E S6 CC BT  
 No trees available in the Southwest quadrant.  
 Distance to the Western Larch BT taken electronically due to length and slope.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fence post approximately 5 feet East with Land Survey Monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 15, 1989.

Witnesses: Jeff Petersen and Rick Robinson.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept. County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office for record on the 27th day of October, 1989  
 David H. Kumbien (COUNTY OFFICIAL) by Kathleen K. Amosbery (DEPUTY)

**RECEIVED BY**

Form R6-7100-57 (9/71)

Umatilla County Surveyor

\*GPO-591-971, 1988

Date 10-89  
 Initials KA  
 No. 89-101-B