


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-171

History of original corner establishment: Corner established in 1882 by Hermon D. Gradon, under General Land Office Contract No. 452.

Surveyor General Records (Notes) states: Set a basalt stone 14 x 10 x 8 ins. 9 ins. in the ground for closing corner to Secs. 5 & 6. Marked CC with 5 notches on E and 1 notch on W edges, from which: A fir 12 in. diam. bears N 15°W 19 lks. dist. marked TIN R36E S32 BT. A pine 12 in. diam. bears S 65°E 154 lks. dist. marked TIS R36E S5 BT. A fir 16 in. diam. bears S 50°W 48 lks. dist. marked TIS R36E S6 BT



(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 14 x 10 x 8 in. basalt stone set in ground in mound of stone marked CC with 5 notches on East and 1 notch on West edges.

Found down fir, 24 in. diam. bearing approximately S 50°W 32 ft. dist. from stone, blaze grown over.

Found rotten fir log, bearing approximately N 15°W 13 ft. dist. from stone.

Accepted stone as corner position.

Description of monument and accessories established to perpetuate the original location of this corner


Set 30 in. x 2 in. iron pipe with 3 in. brass cap marked as shown 20 in. in the ground and raised a mound of stone around pipe for the closing corner between Sections 5 & 6, from which new BT's -

A ponderosa pine 24 in. diam. bears N 4°W 69.8 ft. dist. marked TIN R36E S32 BT.

A fir 18 in. diam. bears S 85°E 100 ft. dist. marked TIS, R36E S5 CC BT.

A ponderosa pine 16 in. diam. bears S 50°W 44 ft. dist. marked TIS R36E S6 CC BT.

Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. West from corner with "Attention" sign attached.



Used steel tape and magnetic compass with declination = 20° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1939 DOUGLAS M. FERGUSON 848

Office of Surveyor County of Hartella State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 15th day of July, 1972, at 10 o'clock a.m., (signed) Douglas M. Ferguson by (DEPUTY)

H-171