


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Jacob C. Cooper under General Land Office Contract No. 397.



Surveyor General Records (notes) states:

A mound of earth 5 ft. at base, 2 ft. high with pits, Set post 4 1/2 ft. long 4 in. square, 2 ft. in mound on table land marked T1S S6 on NE, R36E S7 on SE, R35E S1 on SW and S1 on the NW face, 5 notches on the S and 1 notch on the north edges,

From which

- A pine 30 in. diam. bears N30°E, 76 lks. dist. marked T1S, R36E, S6 BT.
 - A pine 22 in. diam. bears N62°W, 72 lks. dist. marked T1S, R35E S1 BT.
 - A pine 20 in. diam. bears S70°W, 92 lks. dist. marked T1S, R35E S12 BT.
- Also a pit in Sec. 7

A double set of corners was established on this line in a subsequent survey.

Description of corner evidence found: (No subsequent remonumentations in county records)

Found 36 in. ponderosa pine, living, in good condition, with scribing clearly visible, bearing N30°E 59.0 ft. dist. from the corner position.

Found 22 in. pine down and rotten with scribing clearly visible, bearing N62°W, 47.5 ft. dist. from the corner position.


Description of monument and accessories established to perpetuate the original location of this corner

Set a 30 in. x 2 1/2 in. iron pipe with brass cap marked as shown, 26 in. in the ground and raised a mound of stone around the pipe for the corner between Sec. 6 & 7.

From which new BT's

- A fir 18 in. diam. bears S40°E, 14.2 ft. dist. marked T1S, R36E, S7 BT.
- A fir 14 in. diam. bears N45°W, 25.5 ft. dist. marked T1S, R35E, S1 BT.

Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. North from corner with Forest Boundary sign attached.



REGISTERED PROFESSIONAL LAND SURVEYOR

Used steel tape and magnetic compass with declination = 20°E.

Signature of Douglas M. Ferguson, OREGON JULY 17, 1972 DOUGLAS M. FERGUSON 848

Office of [Signature] County of [Signature] State of [Signature], I hereby certify that the within instrument was filed in this office for record on the [Signature] day of [Signature], 1972, at [Signature] o'clock [Signature] m., (signed) [Signature] (COUNTY OFFICIAL) by [Signature] (DEPUTY)