

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-25

History of original corner establishment:

Corner was originally established by Jacob C. Cooper under GLO Contract No. 397, dated July 1, 1881. Survey General Records state: A tamarack 12 ins diam on the S side of mountain, 200 ft. below the summit in dense young timber which I marked for the 1/4 Sec Cor, marked 1/4S on the East and West faces from which

A fir 6 in diam bears S28°E 14 lks dist marked 1/4 S BT.

A pine 12 in diam bears N78°W 22 lks dist marked 1/4 S BT.

Resurveyed by Douglas M. Ferguson, OPLS 848 in 1972. His record states: Found a 24 in. tamarack with grown-over blazes on 4 sides, live, in good condition. Found a 24 in. fir, live in good condition, with scribing visible, bearing S28°E 9 ft. from corner tree. Found a 24 in. pine stump with scribing faintly visible, bearing N78°W 14 ft. from corner tree. No monument set as

Description of corner evidence found: tree is in good condition, for East 1/4 Cor. Sec. 12. From which a new BT, a tamarack 20in. diam. bears S87°W, 63.5 ft. dist. marked T1S, R36E, 1/4S 12 BT. Distance taken to a brass washer in the blaze of the tree. Set a steel fence post approximately 5 ft. west from original corner tree with Forest Boundary sign attached.

Description of corner evidence found:

Corner tree, 24" tamarack, dead, with healed blaze on North. A 24" douglas fir bears S 32° E - 9 feet with healed blaze. A 20" tamarack bears S 87° W - 63.5 feet with healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Reference monument, a 2 1/2" x 30" aluminum pipe with a 2 1/2" aluminum cap, bears N 63° W - 8.0 feet from corner tree, 24" in the ground, marked as shown in corner diagram.

New bearing tree established:


A 5/8" x 30" iron pin with yellow plastic cap bears S 23 1/2° W - 7.6 feet. A 24" white fir bears N 69° W - 114.7 feet, scribed: 1/4 S12 BT.

Bearing tree has a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached 54-3 and 54-9 signs, painted face of blaze red and 6" red band around the bearing tree.

Attached 54-3 sign to iron pin. Set steel fence post near iron pin with 54-9 sign attached. Bearings and distances measured to corner.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on July 21, 1994.

Compass declination 18° East.



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of... Surveyor... County of... Umatilla... State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... 7... day of... December... 19... 94... (COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor Date: 12-94 Rec'd By: RK No. 94-170-B