


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-21

History of original corner establishment:  
Corner originally established by Herman D. Gradon under GLO Contract No. 452, dated June 16, 1882. Surveyor General record states: Set a basalt stone 20 x 12 x 3 ins 15 ins in the ground for cor to sec 11, 12, 13 & 14, marked with 4 notches on S. and 1 notch on E. edges, from which A pine 22 ins diam. bears S.20°E. 250 lks dist. marked T.1S. R.36E. S.13 B.T.



**Description of corner evidence found:**

Found a small mound of stone on steep hillside with a record dimension stone lying loose downhill from the mound. Mound tied by survey and accepted. From which: A 30" ponderosa pine, healthy, with mostly healed blaze bears (record S 20° E - 250 lks ) S 29½° E - 164.6 feet. There appears to be some chisel work on the found stone.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set a 2½" aluminum cap on a 2½" x 30" aluminum pipe, 20" in the ground, with mound of stone to cap. Placed record stone alongside, some chisel marks visible. Cap marked as shown in corner diagram.  
Set a steel fence post with 54-2 and 54-9 sign, 3.3 feet West of monument.  
New Accessories:  
A 5/8" x 30" iron pin with yellow plastic cap bears N 44° E - 20.2 feet.  
A 5/8" x 30" iron pin with yellow plastic cap bears S 45° W - 17.7 feet.  
A 5/8" x 30" iron pin with yellow plastic cap bears N 89° W - 19.2 feet.  
Attached 54-3 sign to iron pins. Set steel fence posts near each iron pin with 54-9 signs attached.

I hereby certify that the above corner was properly monumented to U.S.F.S. standards by me on September 28, 1994.

Compass declination 18° East.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Willi. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 12-31-94*

Office of Surveyor County of Umatilla  
State of Oregon I hereby certify that the within instrument was filed in this office  
for record on the 27 day of December, 1994  
David H. [Signature] by \_\_\_\_\_ (DEPUTY)  
(COUNTY OFFICIAL)

**RECEIVED BY**

Umatilla County Surveyor

Date 12-94

Rec'd By KK

No. 94-170-B