


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.

Surveyor General Records (Notes) states:
Set a basalt stone 14 x 10 x 4 ins. 9 ins. in the ground, for 1/4 cor. marked 1/4 on N face from which:
A tamarack 14 in. diam. bears N60°W 48 lks. dist. marked 1/4 S BT.
A fir 8 ins. diam. bears S70°E 1/4 lks, dist. marked 1/4 S BT.



5-3


(No subsequent remonumentations in county records)

Description of corner evidence found:

- Found 14 x 10 x 4 in. stone with 1/4 marked clearly on face.
- Found 14 in. tamarack with all scribing clearly visible, bearing N60°W 31.6 ft. from the stone.
- Found rotten fir log bearing S70°E 9.2 ft. from the stone.
- Accepted stone as corner position.

Description of monument and accessories established to perpetuate the original location of this corner

Set 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown, 26 in. in the ground and placed original stone North and alongside pipe for the 1/4 corner between Sections 7 & 18, from which new BT's
A fir 9 in. diam. bears N27°E 8.6 ft. dist. marked T1S R36E 1/4 S7 BT.
A ponderosa pine 12 in. diam. bears S48°W 28.6 ft. dist. marked T1S R36E 1/4 S 18 BT.
Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. North from corner with Forest Boundary sign attached.



Used steel tape and magnetic compass with declination = 20° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

Office of *Surveyor* County of *Washtenaw*
State of *Michigan*, I hereby certify that the within instrument was filed in this office for record on the *12th* day of *April*, 19*72*, at *10* o'clock *am*, (signed) *Douglas M. Ferguson* by *Douglas M. Ferguson* (DEPUTY)