


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.



Surveyor General Records (notes) states:

Set a basalt stone 16 x 7 x 7 in. 11 in. in the ground for Cor. to Secs. 7, 8, 17 & 18, marked with 4 notches on S and 5 notches on E edges, from which

A pine 12 in. diam. bears N10°E 140 lks. dist. marked T1S R36E S 8 BT.

A pine 26 in. diam. bears S40°E 100 lks. dist. marked T1S R36E S17 BT.

A pine 6 in. diam. bears S70°W 175 lks. dist. marked T1S R36E S18 BT.

A pine 12 in. diam. bears N5°W 106 lks. dist. marked T1S R36E S7 BT.

J-5

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 35 in. ponderosa pine, live in good condition with healed over blaze clearly visible, bearing N10°E 92.3 ft. from the corner position.

Found a 30 in. ponderosa pine, live in good condition, with blaze chopped open and scribing clearly visible, bearing N5°W 70 ft. from the corner position.


Description of monument and accessories established to perpetuate the original location of this corner

Set a 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown, 28 in. in the ground for the corner to Sec. 7, 8, 18, & 17, from which new BT's-

A pine 30 in. diam. bears S32°E 60.9 ft. dist. marked T1S R36E S17 BT.

A pine 12 in. diam. bears S 54°W 138.7 ft. dist. marked T1S R36E S18 BT.

I rescribed original BT--a 36 in. pine bears N10°E 92.3 ft. dist. marked T1S R36E S8 BT. Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. North from Corner with "Attention" sign attached.



REGISTERED PROFESSIONAL LAND SURVEYOR

Used steel tape and magnetic compass with declination = 20° East.

OREGON JULY 12, 1963 DOUGLAS M. FERGUSON 848

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 15 day of July, 1975, at 10 o'clock am. (signed) Douglas M. Ferguson (COUNTY OFFICIAL) [Signature] (DEPUTY)