

USDA-FOREST SERVICE

Index File No. J-09

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_

Cor. No. \_\_\_\_\_


T 15 R. 36 E

R.D. WALLA WALLA County UMATILLA

Merid. Wm

N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

3 1/4" BLM BRASS CAP ON 2 1/2" IP RISING 4"

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

28" P. PINE, BLAZE HEALED ON ORIGINAL BT, IN - NW QUADRANT.

13" W. FIR, B&S T15 R36 S9 BT, BEARS N 75 1/4° E, 14 LKS., 9.2 FT.

14" D. FIR, B&S T15 R36 S16 BT, BEARS S 35° E, 43 LKS., 25.4 FT.

9" P. PINE, B&S T15 R36 S17 BT, BEARS S 20 1/4° W, 9 1/2 LKS., 4.4 FT.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

Signature

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

FROM INTERSECTION OF RAILROAD & BUTCHER CREEK NESTERLY UP OPEN RIDGE TO POSTED LINE - NORTH ALONG POSTED LINE 250' TO CORNER. CORNER IS ON NE'LY SLOPE 100' INTO WOODS

Signature

*Stallion*

Title

LS 1848

Division

Headquarters

Date

7-23-85

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

NONE

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

SET STEEL FENCE POST 3 FT. WEST OF CORNER.

ATTACHED SIGNS TO POST & BT'S.

Work Done By B.A. SUTTON Title SURVEYOR Date 7-23-85 State Registration No. LS 1848  
or Agency

Certified Cor. Record Prepared? Yes No  Filed At:

Date

REMARKS

Index File No.

J-09

T.

15

R.

36E

M. WM

Tract or Surv. No.

GPO: 1982 O-382-659

Cor.

8/9  
17/16