


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

I-25

History of original corner establishment:

Corner was originally established by Jacob C. Cooper, under GLO Contract No. 397, dated July 1, 1881. Surveyor General Records state: A fir 10 in. diam on steep N mountainside, 200 ft. above creek, in young fir timber, which I marked for 1/4 Sec Cor, 1/4 S on the E & W faces, from which: A fir 4 in. diam. bears N28°W 11 lks dist. marked 1/4 S. BT. A fir 12 in. diam. bears S29°E 9 lks dist. marked 1/4 S. BT.



U.S. Deputy Surveyor, Henry Meldrum, performed a retracement of the West boundary of Range 37 East, under GLO contract no. 450, dated June 11, 1882. He referenced the corner position in his notes.

Description of corner evidence found:

Nothing found of original corner or bearing trees. Re-established by single proportionate measurement, using U.S. Deputy Surveyor, Henry Meldrum's record, under GLO contract no. 450, dated June 11, 1882.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, 20" in the ground with mound of stone to cap, marked as shown in corner diagram. Set steel fence post with 54-9 sign, 2.0 feet North of monument. From which:
A 14" douglas fir bears N 10° W - 35.3 feet, scribed: 1/4 S13 BT.
A 15" douglas fir bears N 17° W - 37.6 feet, scribed: 1/4 S13 BT.
A 8" white fir bears N 72° W - 55.0 feet, scribed: 1/4 S13 BT.
An XBO on base of 1' x 2' x 1' moss covered basalt outcrop, bears N 86° W - 17.6 feet, to the 'X'.
New bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of blaze. Attached 54-3 and 54-9 signs, painted 6" red band and face of blaze red.

I hereby certify that the above corner was properly monumented to U.S.F.S. standards by me on October 10, 1994.

Compass declination 18° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

Office of Surveyor County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 3 day of December, 1994
David H. Wells by _____
(COUNTY OFFICIAL)

(DEPUTY)
RECEIVED BY

Umatilla County Surveyor

Date 12-94

Rec'd By KK

No. 94-170-B

Form R6-7100-57 (9/71)

*GPO-591-971, 1988