

USDA-FOREST SERVICE

Index
File No. N-02


T 1S R. 36E
Merid. WILLAMETTE

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

R.D. WALLA WALLA County UMATILLA
N.F. UMATILLA State OREGON

Tract or
Survey No. _____
Cor.
No. _____

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

3 1/4" BLM BC RISING 23" IN MOUND OF ROCK

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

7 1/2" P. PINE, BLAZED & SCRIBED W 1/16 S 18 BT,
BEARS N 41° E - 59 LKS - 38.9 FT.

7" D. FIR, BLAZED & SCRIBED W 1/16 S 19 BT,
BEARS S 49 1/2° W - 44 LKS - 29.0 FT.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

At South END of Clearing, 200' EAST of Creek
Road 3033 to Fence and Posted Line
North of Corner. Walk South along Posted
line to Corner.

Signature
B. Sutton

Title
LS 1848

Division _____
Headquarters _____

Date
7-85

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

NONE

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set Steel Fence Post 3⁰ft North
Attached Signs to Post and Bearing Trees
Painted 6" Red Band on BT'S

Work Done By B.A. SUTTON Title SURVEYOR Date 7-85 State Registration No. LS 1848
or Agency

Certified Cor. Record Prepared? Yes No Filed At:

Date

REMARKS

Index File No.
N-02

T. 15

R. 36E

W.M.

Tract or Surv. No.

Cor. 318
W 1/16 319