


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

37

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.



Surveyor General Records (notes) states:

- Set a basalt stone, 15 x 10 x 4 ins. 10 ins. in the ground for Cor. to Secs. 13-14-23 & 24, marked with 3 notches on S and one notch on E edges, from which
 - A pine 5 ins. diam. bears N 48° E 26 1/2 lks. dist. marked T1S, R36E S13 BT.
 - A fir 24 ins. diam. bears S 75° E 162 lks. dist. marked T1S, R36E S24 BT.
 - A fir 12 ins. diam. bears S30°W 130 lks. dist. marked T1s R36E S 23 BT.
 - A fir 8 ins. diam. bears N84°W 96 lks. dist. makred T1s R36E S14 BT.

N-21

(No subsequent remonumentations in county records)

Description of corner evidence found:


Found 18 in. fir snag with scribing clearly visible bearing S30°W 86 ft. dist. from corner position.

Found a 15 x 10 x 4 ins. basalt stone with 3 faint notches, laying flat 1 ft. West from corner position.

Description of monument and accessories established to perpetuate the original location of this corner

Set 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown 30 in. in the ground and placed original stone North and alongside pipe for the corner to Sections 13, 14, 23 & 24, from which new BT's-

- A fir 12 in. in diam. bears N38°E 44 ft. dist. marked T1S R36E S13 BT.
- A fir 16 in. diam. bears S70°E 36.1 ft. dist. marked T1S R36E S24 BT.
- A fir 9 in. diam. bears S72°W 66.5 ft. dist. marked T1S R36E S23 BT.
- A fir 14 in. diam. bears N20°W 12.4 ft. dist. marked T1s R36E S14 BT.



Distances taken to a brass washer in the blaze of each BT. Set a steel fence post approximately 5 ft. East with "Attention" sign attached. Corner on steep West slope above Owsley Creek.

Used steel tape and magnetic compass with declination = 20° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1929
DOUGLAS M. FERGUSON
848

Office of Surveyor County of Wasatch
State of Utah, I hereby certify that the within instrument was filed in this office for record on the 14 day of Nov, 1972, at 10 o'clock a.m., (signed) Douglas M. Ferguson by _____ (DEPUTY)