

T-9

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Herman D. Graydon under G.L.O. contract number 452 dated June 16, 1882.

Surveyor General's records state:

Set a post 3 ft long 3 ins square 2 1/2 ins in the ground for the 1/4 sec cor marked 1/4 S on west face from which:

A fir 5" diam bears N 29° E., 2 lks dist marked 1/4 S BT
A fir 18" diam bears N 45° W., 13 lks dist marked 1/4 S BT



T-9

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" in the ground with a 6' steel fence post alongside with signs 54-4 and 54-2 attached.

New bearing trees:

A larch 12" diam bears N 82° W., 19.1 ft dist marked 1/4 S 29 BT
A fir 9" diam bears N 53° E., 15.2 ft dist marked 1/4 S 28 BT

Brass cap is marked: T 1 S R 36 E
1/4
S 29 S 28
R P E 2 8 0 8
1976



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)