


H-157

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

23

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.

Surveyor General Records (Notes) states:
Pine post 4' long 3" thick 2' in ground from which a pine 15" dia. bears N14⁰E 138 lks. dist.
A fir 20" dia. bears S14⁰W 75 lks.



2-19

(No subsequent remonumentations in county records)

Description of corner evidence found:


Found 24 in. ponderosa pine, live in good condition, marked 1/4 S, positioned 1/4 corner between Section 35 and 2, S14⁰W, 91 ft. dist. from notch in blaze.

Description of monument and accessories I established to perpetuate the original location of this corner

Set 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown 6 in. in the ground to solid rock and chiseled an "X" in rock under pine for the 1/4 Section Corner between Sections 35 & 4, and raised a mound of stone 4 ft. in diam. and 2 1/2 ft. high around the pipe, from which new BT's -

A 20 in. fir bears S60⁰W 86.9 ft. marked T2S R36E 1/4 S2 BT. Measurement taken to a brass washer in face of blaze. Set steel fence post approximately 5 ft. west with warning sign attached.

Used steel tape and magnetic compass with declination = 20⁰ East.



REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 12, 1953
DOUGLAS M. FERGUSON
848

Office of Surveyor County of Washtenaw
State of Michigan, I hereby certify that the within instrument was filed in this office for record on the 15 day of April, 1972, at 10 o'clock am, (signed) Douglas M. Ferguson by Douglas M. Ferguson (DEPUTY)

H-157