


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

F-1

History of original corner establishment:

None. Corner was established as part of this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" aluminum cap on a 2½" x 30" aluminum pipe, 15 inches in the ground with mound of stone to cap, marked as shown in corner diagram. Set a steel fence post with sign 54-2 and 54-9 attached, 3.8 feet North of monument.

From which:

A 6" white fir bears N 8° E - 32.3 feet, scribed: N1/16 S7 BT.

A 15" tamarack bears S 7 3/4° E - 10.7 feet, scribed: N1/16 S7 BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached 54-3 and 54-9 signs, painted face of blaze red, and 6" red band around each bearing tree.

I hereby certify that the above corner was properly monumented to U.S.F.S. standards by me on November 3, 1994.

Compass declination 18° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 12-31-94

Office of Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 7 day of December, 1994
David H. Kline by _____
(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor

Date 12-94

Rec'd By KK

No. 94-170-B