


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:

Set basalt stone 18x8x4 ins 12 ins in ground for 1/4 sec cor marked 1/4 on W face from which;

A fir 36 in diam bears N58°E 91 lks dist marked 1/4 S BT  
 A fir 18 in diam bears N33°W 221 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.

**Description of corner evidence found:**

Found a stone 18x8x4 marked 1/4 on West face in a mound of stone.

Found a 38 inch diameter Douglas Fir N58°E, 91 lks, dead, down and sawn open with no marks visible.

Found a 24 inch diameter Douglas Fir N33°W, 221 lks, dead, down and sawn open with no marks visible.

**Description of monument and accessories I established to perpetuate the**

**original location of this corner:** In place of the found original corner stone, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 20 inches in the ground, from which:


**New Bearing Tree and Bearing Object;**

A 26 inch diameter Douglas Fir bears S89°E, 169.61 feet marked 1/4 S11 BT  
 A 1/2"x24" iron pin with plastic cap marked BGA MARKER bears S23°W, 10.78 feet in a small mound of stone.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.  
 Attached a 54-3 sign to the new bearing object.  
 Set a steel fencepost approximately 5 feet North with land survey monument sign attached.  
 Buried the original corner stone North and alongside of monument.  
 Raised a mound of stone around monument, 3 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on September 7, 1989.

Witnesses: Rick Robinson and Jeff Petersen



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 27<sup>th</sup> day of October, 1989  
David H. Kaumbain by Kathleen K. Ambrey  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

\*GPO-591-971, 1988

RECORDED BY  
 INDEXED BY  
 FILED BY  
 No. 89-106-R