

USDA-FOREST SERVICE


Index
File No. J-1
T 1S R. 37E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor. No. _____
Umatilla
R.D. Walla Walla County _____
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None. This corner was re-established by single proportionate measurement, using U.S. Deputy Surveyor, Henry Meldrum's record under GLO contract no. 450, dated June 11, 1882.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on extremely steep East slope 150 * feet m/l West of drainage at West edge of timber. Approximately 2200 feet South of USFS road no. 3113-040.

* Signature

Walli R. Wells

Title

PLS

Division

Headquarters

PENSLERON

Date

9/30/94

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

A 2½" aluminum cap on 2½" x 30" aluminum pipe, 20" in the ground, with a mound of stone to cap, marked as shown in corner diagram. Set a steel fence post with 54-2 & 54-9 signs 1.7 feet North of monument.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 12" douglas fir bears N29°E-40.1 feet, scribed: T1S R37E S7 BT. A 15" douglas fir bears N46½°E-62.2 feet, scribed: T1S R37E S7 BT. A 16" douglas fir bears S31°E-32.1 feet, scribed: T1S R37E S18 BT. A 13" ponderosa pine bears S12½°E-71.3 feet, scribed: T1S R37E S18 BT. Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached 54-3 & 54-9 signs, painted face of blaze & 6" band, red, around each bearing tree.

Work Done By. WR Wells Title PLS Date _____ State Registration No. PLS 1106
 or Agency _____
 Certified Cor. Record Prepared? Yes No _____ Filed At: UMATILLA COUNTY SURVEYOR'S OFFICE Date 12/94

REMARKS

This corner was monumented as part of a USFS contract.

Index File No.	T.	R.	M.	Tract or Surv. No.	Cor.	12
J1	1S	37E	Willamette			13