


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:

Set post 3 ft long 3 ins square 24 in in ground for ¼ sec cor marked ¼S on N face from which;

A tamarack 15 in diam bears S50°E 24 lks dist marked ¼S BT
 A tamarack 15 in diam bears N74°E 23 lks dist marked ¼S BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found the rotted remains of the original corner post to a depth of 12 inches.

ORIGINAL BEARING TREES

Found a 15 inch diameter Western Larch N74°E, 23 lks. dead and down with scribes visible.

Found a 16 inch diameter Western Larch S50°E, 24 lks. dead and standing with scribes visible.

Description of monument and accessories established to perpetuate the

original location of this corner: In place of the original corner post, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 29 inches in the ground, from which:

New Bearing Trees:


A 13 inch diameter Western Larch bears East, 30.68 feet marked ¼ S29 BT
 A 13 inch diameter Western Larch bears S15°W, 62.37 feet marked ¼ S32 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet East with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 2, 1989.

Witness: Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Gr Survey Dept County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 27 day of October, 1989
 Witness Richard Robinson by Kathleen K. Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Clerk
 Date 10-89
 Book KA
 No. 89-106-R

*GPO-591-971, 1988