

**OREGON CORNER RESTORATION FORM**

Section 31 Township 3N  
County Umatilla Date: 01/15/10

Range 29E

Corner Designation: 3N29Z5

Corner common to sections 31,32 T3NR29E, 5,6, T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by David P. Thompson. He set a post in a mound of earth in 1859.

**Monuments and Accessories Found: (Condition and Source)**

- A 2 3/8" Brass cap w/ 951 stamp, no record.
- A 1/2" Iron rebar w/ypc 951LS lies N 67°00' E, 114.52'.
- A 1/2" Iron rebar w/ypc 951LS lies N 18°00' E, 41.26'.
- A 1/2" Iron rebar w/ypc 951LS lies N 33°15' W, 44.33'.
- A 1/2" Iron rebar w/ypc 951LS lies N 66°15' W, 82.61'.

Diagram



Sketch



2 3/8" BC



NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N740008.02  
E8527770.39  
LAT - 45° 41' 21.78268" N  
LON - 119° 13' 31.9412738" W

**Monument (s) Set (Procedures and Description)**

None

**References Set:**

None

**Location and Comments**

The corner is 1/2 mile West of cattle guard near the South end of Snow Road and 45 feet South of old fence.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 3-10  
Rec'd By: KK  
No. 10-77-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11