

OREGON CORNER RESTORATION FORM

SECTION: 10 TOWNSHIP: 2N RANGE: 29E J-17

COUNTY: UMATILLA DATE 8/2010

CORNER DESIGNATION

SE 10

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Thompson under Contract #83 in 1859. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Nothing found.

MONUMENT DETAIL

T2N R29E
10|11
15|14
2008
LS 951

OREGON STATE PLANE COORDINATES NORTH ZONE, NAD 83(91), Int Feet:

729875.47
8543918.75

MONUMENT SET (PROCEDURES AND DESCRIPTION)

In a N-S fence line for Eastings and by proportion for Northings I set a 2 3/8" brass cap on a 1" x 30" iron pipe at ground level stamped as above.

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 63° 42' 14" W 68.32'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 1° 27' 47" W 153.85'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 1° 59' 53" E 67.56'
An 8" bridge spike and blue mag. 12" below surface bears S 51° 10' 28" W 61.00'
These bearings and distances are State Plane.

LOCATION AND COMMENTS

From Cunningham sheep ranch shop go southwesterly on Cunningham Road 2.7 miles to fork. Take right fork and go southwesterly 1 mile to corner in a N-S fence line at a corral.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: G. EDWARDS
WITNESS: R. SMITH

