

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. A-1

Notes: Monument marked as shown below

History of original corner establishment:

This corner was originally established by J. Burnett, U.S. Deputy Surveyor, under Contract No. 97, dated September 12, 1860. The original notes state that at the corner a wood post was set with charred stake, earth mound and pits.

In 1904, this corner was recovered and used by Surveyor John Kiebrell in County Survey No. 212.



Corner No. Compass Declination: 18.0

Description of corner evidence found:

Found earth berm from old fences which once extended east and west, and an existing north-south fence line. The ground west of the corner area has been farmed for many years. There is no evidence left of the original post, mound, charred stake, or pits. After making measurements to available corners west, east, and south, and to a road intersection 1/2 mile to the north, and finding that the measurements match the original record within reason, I accept the four way fence intersection as the best remaining evidence of the original corner location.

Description of monument and accessories I established to perpetuate the

original location of this corner:

At the position of the four way fence intersection, I set a 2 1/2" brass cap on 1 1/2" by 30" galv. iron pipe 24" in the ground and surrounded with a mound of earth. Set two reference monuments referencing the new corner monument. From the corner monument:

A 1 1/2" yellow plastic cap marked " W.R. Wells, PLS 1106", set on a 5/8" by 30" iron rod bears S3°E 15.49'.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears N3°W 16.27'.

Both reference monuments are set near the north-south fence line.


Attached witness corner sign on the fence post south of the corner monument. Set steel fence posts near each reference monument and attached witness corner and bearing object sign.

The aluminum cap on the reference monument is marked:

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106



Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

88-19-C