

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/03/06

CORNER DESIGNATION: 2N31, C-17, The West One-Quarter Corner of Section 2.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1
4
S3 | S2
2006
PLS 1106

MONUMENT SET:

Accepted field line intersection with field lines running North and West as best remaining evidence of the original corner location. At reestablished corner location, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level in farmed field lines between fields. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 52° East, 36.5 feet.
 - A blue Deep-1 magnet buried 22" below ground level bears South 36 1/2° East, 38.0 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 45° West, 38.1 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 35 1/2° West, 30.7 feet.
- Buried bearing object signs with all magnets. Set steel fence post with witness sign attached 1 foot North of monument.

LOCATION AND COMMENTS: Corner is located in a farmed field at the intersections of field lines or berms North and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 738773.33
E = 8607821.09

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31C17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08