

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/15/06

CORNER DESIGNATION: 2N31, C-9, The West One-Quarter Corner of Section 4.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND:

Found and held a 1" diameter by 31" long pointed steel shaft with rod weeder chain link welded to it at the top as best remaining evidence of the original corner. North-South field line and East-West field berms run through the corner point.

MONUMENT MARKING DETAIL:

T2N R31E
1
4
S5 | S4
2006
PLS 1106

MONUMENT SET:

At the position of the found steel shaft set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 12" below ground level. Buried the steel shaft on the East side of the brass cap monument with its top 4" below the brass cap. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 20" below ground level bears North 39° East, 24.5 feet.
 - A blue Deep-1 magnet buried 20" below ground level bears South 37° East, 27.5 feet.
 - A purple Deep-1 magnet buried 20" below ground level bears South 36° West, 27.1 feet.
 - An orange Deep-1 magnet buried 20" below ground level bears North 40° West, 26.0 feet.
- Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located at the intersection of a farm field running North-South and a field berm running East-West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 738546.91
E = 8597214.82

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31C9



renews 6-30-08

06-462-C