

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/21/06

CORNER DESIGNATION: 2N31, E-11, The South One-Quarter Corner of Section 4.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner and raised stone mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND:  
Found and held a old rock jack and mound of stone as best remaining evidence of the original corner. There are rock jack remains of fence East-West through the corner and down wood fence posts extending North.

MONUMENT MARKING DETAIL:

T2N R31E  
1 S4  
4 S9  
2006  
PLS 1106

MONUMENT SET:

At accepted corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe 18" in the ground to bed rock and raised a mound of earth and stone to the top of the cap. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 34° East, 32.8 feet.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 54° East, 30.3 feet.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 56 1/2° West, 45.1 feet.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 60 1/2° West, 52.5 feet.

Attached bearing object signs to all rebar accessories. Set steel fence post with witness sign 2 feet East of corner.

LOCATION AND COMMENTS: Corner falls on a rocky South facing slope with fence remains East, West and North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 735922.52  
E = 8600016.73

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31E11

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*

*06-462-C*