

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/23/06

CORNER DESIGNATION: 2N31, E-17, The Northeast Corner of Section 10.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for corner to Secs. 2, 3, 10 and 11, drove charred stake and raised mound with trench, as per instructions. The corner was recovered by G. Kimbrell in survey recorded at Book 1, Page 485.

MONUMENT AND ACCESSORIES FOUND:

Found and held a 2 3/8", unstamped brass cap on 1 1/4" galvanized iron pipe. Cap protrudes 4" above ground. The origin of this monument is unknown. There are old down wood fence posts, (no wire) East and West of the monument.

MONUMENT MARKING DETAIL:

T2N R31E
S3|S2
S10|S11
2006
PLS 1106

MONUMENT SET:

I marked the found brass cap as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 20° East, 43.3 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 40° East, 42.2 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 35° West, 46.9 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 57° West, 56.0 feet.

Attached bearing object signs to all rebar accessories. Attached witness sign to steel fence post set 3 feet North of monument.

LOCATION AND COMMENTS:

Corner is located on bear South slope near top of hill approximately 100 feet South of the edge of a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 736127.37
E = 8607932.91

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31E17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renew 6-30-08