

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/23/06

CORNER DESIGNATION: 2N31, E-19, The North One-Quarter Corner of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1 S2
4 S11
2006
PLS 1106

MONUMENT SET:

Held railroad tie fence corner with fences South and West as best remaining evidence of original corner position. There are remains of a fence extending East, (rock jacks). A old abandoned power pole line runs East-West through this corner, (evidenced by old glass insulators and wood pole cross arms, and a few standing abandoned power poles). At a point just North of the railroad tie fence corner set A 1 1/4" x 30" galvanized iron pipe with a 2 3/8" brass cap, 24" in the ground and surrounded with earth and stone. Monument marked as shown in Monument Marking Detail.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 56° East, 41.9 feet.

A 5/8" x 24" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South, 36.2 feet.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in a abandoned power pole North 82° West, 24.9 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 31° West, 57.5 feet.

Attached bearing object signs to rebar accessories and abandoned power pole with brass washer. Attached witness sign to railroad tie by monument.

LOCATION AND COMMENTS:

Corner is at a railroad tie fence corner with fences South and West on a steep Southeast slope.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 736189.73
E = 8610485.64

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31E19

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C