

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/19/06

CORNER DESIGNATION: 2N31, E-23, The North One-Quarter Corner of Section 12.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions. John Kimbrell reestablished this corner as a "stone 18x7x6" in survey recorded in Book 1, Page 575.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E

1 S1

4 S12

2006

PLS 1106

MONUMENT SET:

Held a Railroad tie fence corner with fences South and East as best remaining evidence of original corner position. Dug 3 1/2 to 4 feet deep and probed at fence corner for record stone, (by Kimbrell) but did not find it. We did find one broken stone, 10"x7"x6", with no marks. A fiber optic line has recently been laid in this area, buried fiber optic signs and up turned rocks are noted. At a point just North of the railroad tie fence corner post, set A 1 1/4" x 30" galvanized iron pipe with a 2 3/8" brass cap, 26" in the ground. Monument marked as shown in Monument Marking Detail.

From which:

A 5/8" x 24" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 87 1/2° East, 15.7 feet.

A 5/8" x 24" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 87 1/2° East, 47.2 feet.

A 5/8" x 24" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South, 36.7 feet.

A 5/8" x 24" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South, 65.6 feet.

Attached bearing object signs to rebar accessories. Attached witness sign to railroad tie at beside monument.

LOCATION AND COMMENTS:

Corner is at a railroad tie fence corner with fences South and East. The area around this corner farmed and has been disturbed by recent fiber optic line construction.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 736210.12

E = 8615734.88

FIRM: William R. Wells, PLS

P.O. Box 1696


Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31E23



William R. Wells



Renews 6-30-08