

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/2/06

CORNER DESIGNATION: 2N31, G-1, The West One-Quarter Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for 1/4 Sec. corner and build mound of earth with pits, trench & c., as per instructions. John Kimbrell reestablished this corner in survey recorded at Book 1, Page 556, his record states: "set stake for 1/4 Sec. point".

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N
R30E|R31E
1
4
S12| S7
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northwest and Southwest corner of Section 7. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 18" below ground level.

From which:

A Silver Deep-1 magnet buried 24" in the ground bears North 74° East, 33.4 feet.

A Blue Deep-1 magnet buried 24" in the ground bears South 15° East, 31.9 feet.

A Purple Deep-1 magnet buried 24" in the ground bears South 74° West, 32.3 feet.

An Orange Deep-1 magnet buried 24" in the ground bears North 04° West, 28.4 feet.

Buried bearing object signs with all magnets. Attached bearing object sign and witness post sign to wood fence corner post 1340' +/- South of monument.

LOCATION AND COMMENTS: Corner is located in a farmed bottom ground field approximately 1/2 way between the Union Pacific Railroad tracks and the Umatilla River.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 733391.87

E = 8586522.14

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31G1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C